Metrolinx GO Expansion Program Public Consultation #3 Briefing

City of Burlington

Environment, Infrastructure & Community Services


Committee

December 7, 2020

GO Expansion Overview and Service Plan

OVERVIEW OF THE GO EXPANSION PROGRAM

Metrolinx is en route to transform and modernize its rail system with the implementation of the GO Rail Expansion Program - an investment program intended to provide:



This transformation will bring fundamental changes to GO Transit's seven (7) operating rail corridors. It will result in the implementation of over 205 km of new track and 680 km of electrified track that will be laid to allow for the more frequent and efficient movement of trains.

Go expansion – Lakeshore west



Lakeshore West Today

Lakeshore West is GO Rail's most heavily used corridor, with 48,000 peak passengers and 16,000 mid-day, contra-peak, and all-day passengers. Large parts of the corridor have been urbanized since the 1950s but intensification continues especially around Oakville and Aldershot stations.

The Lakeshore West Line currently offers two-way all-day service between Union Station and Aldershot with trains arriving every 15-20 minutes in the peak period and every 30 minutes throughout the rest of the day and on evenings and weekends. Additionally, there are trains to Union Station from Hamilton in the morning and trains from Union Station to Hamilton in the evening.





Table 3.2: GO Expansion Improvements to the Lakeshore West Line

Program Element		Performance Objectives	Next Steps
* 2	MORE ACCESSIBLE STATIONS	Customers can board and alight faster, reducing trip times by 2-5 minutes	 Improvements at: Exhibition, Mimico, Long Branch, Clarkson, Oakville, Bronte, Appleby, Burlington
*	MORE ALL-DAY SERVICE	 282 weekday services Detailed service plan shown in Figure 3.5 Two-way all-day service between Union and Hamilton, fifteen minute service or better between Burlington and Union 	 20.4 km of new track, two new road/rail separations All-day EMU service comprises 2 tph stopping at all stations to/from Burlington, and 2 tph stopping at all stations to/from Oakville. All-day Aldershot trains stop at Burlington, Bronte, Appleby, Oakville and Clarkson offering
€::→	IN BOTH DIRECTIONS		a combined service from these stations, half of which are express from Oakville Oakville and Clarkson have 6 tph, comprising 2 express and 4 all stations. Port Credit and all stations to Union have 4 tph all day
	TRAINS EVERY 15 MINUTES		
	FASTER AND MORE EFFICIENT TRAINS	Up to 8% faster for electric locomotive services	Electrification from Union Station to Burlington Station (205 km of electrified track)
		Up to 29% faster for EMU service	Use of electric rolling stock (locomotives and EMUs)

New Track and Facilities Transit Project Assessment Process (TPAP)

INFRASTRUCTURE REQUIRING TPAP/ADDENDA APPROVAL MAP



New Track and Facilities TPAP:

- A1 New Walkers Line Layover by Appleby GO
- A2 Track Upgrades by Oakville GO
- Track Upgrade by Long Branch GO
- A4 New Turnback Track by Eglinton GO
- Track Upgrades by Whitby GO
- A6 New Third Track, Thickson Rd Bridge Expansion, and New Track and Island Platform at Oshawa GO
- A7 New Track by Allandale GO
- A8 New Track by York University GO
- A9 Track Upgrades, Electrification of Rail Corridor from Union Station to Pottery Rd, and New Don Valley Layover
- A10 New Passing Track, New Side Platform at Mount Joy GO
- A11 New Track, New Island Platform, and New Unionville Storage Yard by Unionville GO

Stouffville Rail Corridor Grade Separations TPAP:

- **B1** Denison St, Road Underpass
- **B2** Kennedy Rd, Road Underpass
- B3 Passmore Ave, Road Underpass**
- B4 McNicoll Ave, Road Underpass
- B5 Huntingwood Dr. Road Underpass
- B6 Havendale Rd, Road Closure with Multi-use Crossing
- **B7** Progress Ave, Road Overpass

Scarborough Junction Grade Separation TPAP:

- C1 Scarborough GO Modification / Relocation
- C2 Rail Bridge Widening at St. Clair Ave E
- C3 Midland Layover
- C4 Stouffville Line Rail-Rail Grade Separation
- C5 Depressed Rail Under Danforth Rd
- Corvette Park Multi-Use Crossing

Network Wide Structures Project:

- D1 Wellington St, Road Underpass**
- D2 McNaughton Rd, Road Overpass

System-Wide Projects:

- Noise and Vibration Assessment
 Update
- Air Quality Assessment Update

*Union Station Trainshed Improvements

** to be explored in a future Addendum

Updated map for Public Consultation Round 3

Walkers Line Layover

The location of the proposed Walkers Line Layover Facility has been shifted since Round 2 of public consultation. The current proposed location is also within the City of Burlington, at a neighbouring property.



Revised Design Elements:

- Staff access has been shifted east along Harvester Road.
- Crew services and parking have been moved to an adjacent property.
- Storage tracks remain within Metrolinx's right-of-way.

Design Elements:

- Electrification infrastructure*
- Storage of 9 GO Trains
- Fleet Storage, Crew Services, and Staff Parking
- Connections to mainline Lakeshore West Corridor track at west and east ends.

Proposed Site Plan

^{*} Electrification of the Lakeshore West Corridor was previously approved as part of the 2017 GO Rail Network Electrification TPAP.

Walkers Line Layover



Walkers Line Layover

Future Work Commitments

Although the anticipated effects and proposed mitigation measures presented during Public Information Centre #2 are still largely valid for the newly-proposed location, the following additional activities will be completed prior to construction:

- A Phase 1 Environment Site Assessment will be completed to determine if there is potential for existing contamination onsite, and whether additional study is needed.
- A Hydraulic Analysis will be completed to determine the impacts of lengthening the existing Shoreacres Creek culvert, and to determine if additional mitigation is required.

Metrolinx will continue to communicate and engage with stakeholders during detailed design and construction planning to address municipal concerns.



Timelines & Consultation

Public Consultation – Open Houses

Round 1 of public consultation was undertaken as a series of <u>in-person</u> open houses from **February 18 to 29, 2020**.

450 Members of the public signed in at events

Written comment forms submitted during the Open Houses

15

Comments submitted after Open Houses by mail or email

Round 2 was a virtual open house held from August 18 to September 1, 2020.

13,000 + Website landi

Website landing page views

173

Comments on all social media platforms

72

Comments and feedback forms submitted on all project pages

The Notice of Commencement for the three (3) TPAPs was issued on **September 8, 2020.**

- Email correspondence to project stakeholders including government ministries, municipalities, conservation agencies, police and fire agencies and school boards.
- Briefings with Elected Officials
- Letters to Indigenous communities
- Mailout to residents within 100m of both sides of the corridors

Open House Round 3

November 27 to December 11, 2020

- *Purpose:* present final EPR and EPR Addenda findings, changes to already presented infrastructure, and additional studies results not presented during rounds 1 and 2, including updates on operational noise, vibration and air quality studies.
- *Materials:* Overview videos, updated project websites, new materials on virtual information panels, links to Environmental Studies and link to round 1 and 2 materials (including: proposed infrastructure panels, information sheets, roll plans)

Notifications:

- Bulk mailer properties within 100m of the study area rail corridor
- Paid and organic social media posts (Facebook, twitter, LinkedIn, Instagram)
- Blog posts on Metrolinx News (online forum)
- Emails to stakeholder groups: PIC#1&2 sign ups, community members, and GRT
- Letters (emailed) to Indigenous communities
- Metrolinx regional newsletters (Toronto West, Toronto East/Durham, Peel, Halton/Kitchener Waterloo, York, and Simcoe Region) via email
- Elected officials letters and offer to meet
- Newly impacted property owner letters

PROJECT TIMELINE - TPAP SPECIFIC

Post-TPAP Phase Pre-TPAP Consultation (2019 - 2020) **TPAP Phase (2020 - Early 2021)** (2021 and beyond) • Prepare background studies, **Development of Notice of Commencement, September 2020** conceptual designs, and impact detailed design assessments and start of Consult with the public, stakeholders, and construction • Consult with the public, stakeholders, Indigenous Nations, Summer - Fall 2020 and Indigenous Nations Document findings in EPR (up to 120 days), • Public Open Houses Round 1, Summer - Fall 2020 February 2020 We are • Document findings and prepare draft Virtual Open House Round 3, here November 27 - December 11, 2020 Environmental Project Report (EPR), which includes: Description of the transit project and **Notice of Completion, Winter 2020/2021** proposed new infrastructure Assessment and evaluation of Public and stakeholder review of EPR (30 days), impacts Winter 2020/2021 Proposed measures to mitigate Minister's review of EPR and impacts Notice to Proceed (up to 35 days), • Virtual Open House Round 2, **Early 2021** August 18 - September 1, 2020 **Statement of Completion, Early 2021**

△ METROLINX